HASSAN DIVISION.

Abstract Notification dated 4th November 1918.

The attention of the public is invited to detail notification dated 24th October 1918, published in page 958 of Part IV of the 42nd issue of the *Mysore Gazette*, wherein tenders for the construction of an additional block in the compound for old High School at Hassan, were called for. The amount to be deposited is Rs. 200. The time fixed already for the receipt of tenders is hereby extended up to the 16th November 1918.

Dated 4th November 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 30th November 1918, for repairing the Jain Basti temple at Halebid, Belur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for repairing the Jain Basti temple at Halebid, Belur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the probable cost of repairing the Basti temple at Halebid, Belur Taluk.

No.	Items of work	Per	Entrance mantapam	Ranga mantapam	Parshwanathaswami temple	Adishwara temple	Santheswaraswami temple	Compound wall
1	Removing the old concrete layer over the terrace	C. ft.	68	595	990	392	1,258	...
2	Relaying fresh concrete in lime mortar ...	"	51	298	495	196	629	...
3	Re-terracing with 2 layers of flat tiles set in cement and lime plaster over it.	Sq.	0·68	11·90	19·77	7·81	25·16	...
4	Removing the existing compound wall rough stone in mud.	L. S.	Rs.	...	...	...	...	...
5	Excavating foundation for compound wall ...	C. yd.	..	...	...	...	..	195
6	Removing the broken slabs and beams with props, etc.	L. S.	Rs.	...	...	...	...	...
7	Replacing new slabs and beams neatly dressed ..	S. ft.	86	...	...	26		...
8	Reconstructing the parapet wall over mantapams with burnt brick in lime including plastering.	R. ft.	16	50	...	25	160	...
9	Filling foundation with rough stone in mud with available stones.	C. ft.	...	...	...	...	...	5,265
10	Burnt brick in clay	"	...	...	...	...	...	3,713
11	Cement pointing	Sq.	3·62	9·45	5·00	...	5·00	...
12	Filling the crevices with small jelly grouting with cement pointing.	"	2·00	5·00	20·00	...	69·08	...
13	Coping with burnt brick in lime 9" height including plastering.	R. ft.	...	...	...	...	...	1,040
14	Repairing the front gate with new frames, etc., painting.	L. S.	Rs.	...	..	...	...	...
15	Flooring with concrete and smooth plastering (6" thick).	C. ft.	..	201	...	...		...
16	Removing the temporary structure built with rough stone in mud.	L. S.	Rs.	...	....	...	...	...
17	Sky ventilators with teakwood frames and masonry as per plan.	Each	...	...	No. 2	....	2	...
18	Plastering with lime mortar	Sq.	...	...	3·00	...	...	62·40
19	Constructing fallen skin wall with existing stones in lime.	C. ft.	...	...	...	225	...	...
20	Filling with brick jelly in lime hearting ...	"	...	...	...	169	...	...
21	Clearing site and removing the rubbish by carting and other unforeseen works if found when execution.	L. S.	Rs.	...	...	...	...	...
22	Scaffolding charges	L. S.	Rs.	...	...	...	...	...

R. W. SCALDWELL,
Executive Engineer.